

LEGEND


- WALLS: PRECAST WALL  
REINFORCEMENT: RL718V CENTRAL
- FOOTINGS:
- BP1 Ø600 BORED PILES x 2000 MIN. DEEP  
REFER TO DRAWING S401 FOR DETAILS
- SF1/SF2 STRIP FOOTINGS  
REFER TO DRAWING S401 FOR DETAILS

NOTES

- FOR FOOTINGS DETAILS REFER TO S300 SERIES DRAWINGS
- FOR EXTERNAL WORKS DETAILS REFER TO CIVIL DRAWINGS

FOOTING SCHEDULE					
MARK	DIAMETER/WIDTH	DEPTH	F <sub>c</sub>	REINFORCEMENT	NOTES
BP1	600	2000	25MPa	-	PLAIN CONCRETE
SF1	750	250	25MPa	Refer to Details on Dwg No. S401	

1	ISSUED FOR CONSTRUCTION	JP	02/08/2024	
A	FOR APPROVAL	JP	24/07/2024	
REV	DESCRIPTION	APP'D	DATE	



**GANDY AND ROBERTS**  
**CONSULTING ENGINEERS**

159 DAVEY ST, HOBART  
TASMANIA, AUSTRALIA 7000  
www.gandyandroberts.com.au  
mail@gandyandroberts.com.au  
ph 03 6223 8877

**NEW WAREHOUSES**  
**14 SPARK DRIVE**  
**CAMBRIDGE 7170**  
DRAWING TITLE  
**FOOTING PLAN**

0	50mm	SCALE
DESIGNER	DRAWN	CHECKED
AT	JP	AT
PROJECT	DRAWING	REVISION
24.0088	S101	1

S:\Drawings\2024\01\08 - 14 Spark Drive Warehouse - G&R Drawing\0187 - Footing Drawing - msp.dwg, msp.dwg, S: 15/11/24

© GANDY AND ROBERTS CONSULTING ENGINEERS